



manufacturers of the finest small elevators since 1986

ELEVATOR CONCEPTS LTD

18720 krause
734-246-4700

riverview, mi 48192
fax 734-246-2547

TYPE X5C ROPED HYDRAULIC ELEVATOR SPECIFICATION

GENERAL

SCOPE OF WORK:

It is the intent of this specification to provide for a complete elevator system, including but not limited to all labor, material, equipment as required to provide a complete elevator as shown on the drawings and specified herein.

SUMMARY OF WORK SPECIFIED ELSEWHERE:

Legal hoistway and machine room, properly dimensioned and enclosed, including landing entrances.
Suitable motor circuit through a heavy duty fused mainline disconnect to the lift controller.
Suitable lighting circuit through a lockable disconnect to the lift controller for cab lighting.
Fire extinguisher in machine room.
Finish floor covering.

SUBMITTALS

Submit shop drawings including basic device layout with clearances, loads on building structure, excavation requirements, machine and motor data, weights of principle components, electrical requirements, and other information as may be required by regulatory agencies.

Submit product data including descriptions and operation of principle components, maintenance schedules, parts lists, operating instructions, and emergency procedures.

CODE REQUIREMENTS

Comply with all applicable requirements of ASME 17.1, and local codes. Provide permits and inspections as required.

GUARANTEE

Provide one year guarantee for materials and workmanship. Make good on defects, except those due to ordinary wear and tear, misuse, or improper maintenance, at no cost to the owner.

QUALITY ASSURANCE

The equipment shall be manufactured as an integrated system and supplied as a complete package from a single supplier. The installer shall have not less than 5 years experience with the installation of equipment similar to that specified.

MAINTENANCE

The installer shall maintain a 24 hour service for repair and maintenance of the equipment. Upon completion of the work, the installer shall provide 90 days free maintenance. Upon completion of the free maintenance period, the installer shall provide to the owner a proposal for continuing maintenance service.

INSTALLATION

The installation shall be first-class in every respect, utilizing trained and licensed personnel experienced with the equipment specified. Comply with all applicable codes. Electric wiring shall comply with the latest edition of the National Electric Code and ASME 17.1.

SYSTEM DESIGN

Provide manufacturer's standard or custom equipment as required to comply with the requirements specified herein.

AS-0X5C Type X5C specification

PRODUCTS:

Elevator contractor to furnish and install where indicated on plans one (1) TIGER LIFT X5C Roped Hydraulic elevator as manufactured by Elevator Concepts LTD, Riverview, Michigan.

SYSTEM DESCRIPTION:

MODEL & TYPE	X5C (commerical) ROPED HYDRAULIC
CAPACITY	1400 #
SPEED	28 FPM
TRAVEL	25' (40' max if allowed by code)
PLATFORM	42" x 60 max
LANDINGS	8 max
CAR OPENINGS	3 max
DOOR SIZE	36" x 80
DOOR TYPE	Swing
OPERATION	Single pushbutton automatic
POWER SUPPLY	208 VAC 30A 1ph

CAB:

WALL FINISH	Laminate
GATE TYPE	Accordion
CEILING FINISH	Laminate
HEIGHT	84"
HANDRAILS	1
FLOOR COVERING	BY OTHERS

FIXTURES:

COP	Standard
CPI	Optional
CDI	Optional
HPI	Optional
HALL STATION	Standard
TEL CABINET	Optional
EMERGENCY LIGHT	Optional
LANTERNS	Optional
FINISH	#4 Stainless standard

CONTROL:

CONTROLLER LOGIC	Relay standard
CONTROL VOLTAGE	24 VOLT
LANDING SYSTEM	MAGNETIC HALL EFFECT SENSOR
PUMP	SUBMERSIBLE SCREW
EMERGENCY LOWERING	Manual standard
INTERLOCKS	GAL SM / GAL N and retiring cam where required
GATE OPERATION	Manual standard
DOOR OPERATION	Manual standard

AS-0X5C Type X5C specification

MACHINE:

Pumping unit to be of unitized construction, including steel reservoir of adequate capacity with cover, direct coupled gear type positive displacement pump, heavy duty submersible motor, elastomeric mounting isolation, unit control valve and line shut off valve.

PUMP:

High tolerance 3 screw set of hard nitrided steel, balanced to eliminate all axial loading. Input shaft to be supported by motor grade roller bearing. Housing to be extruded from G-Al-Si-12 Cu-Mg-Ni alloy, with integral steel strainer.

VALVE:

Hydraulic unit control valve shall be machined from solid aluminum billet, with the following field adjustable functions: check valve, relief valve, up start valve, down start valve, down speed. Unit valve shall be equipped with self closing manual lowering valve, self cleaning strainer, pressure gauge & shut off.

GUIDE RAILS:

Steel T rails shall be machined to exact tolerances for smooth travel. Guides shall be stabilized by adequate brackets as required, and secured to hoistway. Guides shall have a nominal weight of 8 lbs/ft.

ROLLER GUIDES:

Car roller guides shall be consist urethane bonded to a machined aluminum hub, fitted with a roller bearing. The urethane shall be of suitable durometer for elevator service, and shall be machined true after bonding.

BUFFERS:

Compression springs of sufficient stroke and capacity shall cushion the car in the event of overtravel.

CAR FRAME:

Frame shall be constructed of steel, rigidly reinforced and gusseted, bolted and welded to insure durability. Supply isolation coupling between piston and platen. Provide platform of 1-1/4" plywood. All frame components shall be capable of sustaining a static load 5 times the rated load.

CAB:

Cab walls to be 3/4" engineered stressed-skin panels, consisting of high pressure plastic laminate pressure bonded with epoxy to a high density frame with 0-0-10 3/8 vertical core material. Car shall be fitted with a collapsing gate at each opening, conforming to applicable code. Canopy shall be 3/4" stress skin panel, laminate finish with 2 recessed incandescent light fixtures. Canopy shall be capable of sustaining 100 lbs/sq.ft. - 500 lbs total. Provide handrail.

GATE:

Standard gate to be wood folding accordion type, with vinyl hinges. Panels to have stabilized wood core faced with semi-rigid vinyl film, 6 mil minimum, pressure laminated. Panels to be enclosed in steel frames, joined with full length articulated pins. Hanger assembly of dual nylon rollers shall be installed on alternate panels. Gate shall be suspended in track of no less than 20 gauge metal. Gate shall be fitted with lower guide pins and track.

Optional Heavy Duty side slide gate to consist of articulated 5" extruded aluminum panels, each with a total thickness of 5/8". Each panel to have articulation joint with upper and lower bearings, retaining rod and outer tube. Provide wheeled trolley with ball bearing urethane tired wheels on alternate panels. Provide bearings for bottom guide. Provide upper and lower aluminum extruded track, with molded corner sections. Gate to turn and recess behind cab wall.

CONTROLLER:

Controller shall be enclosed in a NEMA 12 cabinet. Shall be of the electro-magnetic type, designed to prevent damage to the motor from overload or excessive current. The controller shall automatically stop the motor and close all valves if any safety device becomes operative. A non interference relay shall be provided. Constant pressure on a car or hall button shall send car to the desired floor if all safety circuits are made up. A low oil timer shall stop the motor and cause the car to descend to the lowest landing if the required travel time is exceeded. Controller and all associated switches and wiring to comply with ANSI 17.1.

AS-0X5C Type X5C specification

FIXTURES:

Provide a car operating panel with buttons for each landing. Provide a car top operation device. Provide a light switch, alarm button, and emergency stop button. Provide a call button at each landing. All fixtures shall have stainless steel face, #4 finish. Operating buttons shall be internally illuminated when depressed and extinguished when call is answered. Buttons shall be 1-1/8" diameter with black bezel. Floor designations shall be 5/8" high, black, on translucent white background.

EMERGENCY OPERATION:

When required, provide backup power source to allow normal elevator operation in the down direction.

JACK UNIT:

The hydraulic jack unit shall comply with all provisions of ASME 17.1. The plunger will be machined true to a minimum smoothness of 12 micro-inches, and equipped with a suitable stop ring. The cylinder will be rated for 500 psi working pressure, and fitted with a safety bulkhead, seamless dished bottom cap, removable head, bearing, and packing, and provisions for air bleed and leakage collection. The jack unit shall be equipped with a U-groove sheave to support hoisting cables. The sheave carriage shall be provided with gibbs to guide it on the car guide rails. Hoisting cables to be 3/8" x 8-19 traction steel.

SAFETY:

Type A instantaneous safety shall be located in a steel safety plank below the platform, capable of stopping and holding the car plus its rated load with a safety factor of 5 minimum. Safety shall be actuated by a slack cable mechanism or optional governor. Safety shall operate a switch to remove power from motor and valve. Safety shall release only by raising the car.

GOVERNOR:

Governor shall be furnished where required by code. Governor shall be of the centrifugal type. The governor rope shall be steel, 1/4" diameter and 8x19 construction. Governor shall be located on the machine base. Tension sheave shall maintain sufficient traction, and be located in the overhead. Safeties shall set through inertia on free fall, independent of the governor.

LEVELING DEVICE:

Provide automatic 2-way leveling device to maintain platform within 3/8" of landing. Leveling device to function when doors and gates are open or closed. Leveling device shall consist of hall effect sensors mounted in a traveling carriage attached to the car, output driver circuit board, 2" spring steel tape with mounting brackets, and sufficient magnets to actuate sensors as required for the appropriate control of the elevator.

AS-0X5C Type X5C specification

EXECUTION:

PREPARATION

1. Verify that hoistway, pit and machine room are ready for installation of elevator equipment.
2. Verify that shaft and openings are according to manufacturer's layout as approved for this installation.
3. Confirm electrical power availability and characteristics; arrange for temporary electrical power if necessary.
4. Report defects or deficiencies in writing.

INSTALLATION

1. Coordinate elevator installation with other trades for time and sequence to avoid delays.
2. Install in accordance with all applicable codes.
3. Install hoistway and machine room components as per manufacturer's recommendations.
4. Provide conduit, boxes, and wiring to connect controller to switches, signals and accessories.
5. Arrange equipment in machine room to allow for future service of individual components. Arrange equipment to allow clear passage to access door; maintain all code clearances.
6. Adjust equipment for proper operation as per manufacturer's recommendations.

TURNOVER

1. Upon completion of installation and before turnover, perform tests as required by the authority with jurisdiction; correct any deficiencies. Furnish test and approval certificates.
2. Instruct Owner's personnel in operation and emergency procedures.
3. Remove protective coverings from finished surfaces; clean all finished surfaces as required.